

Space Solar Power Session , ISDC 2022

Development Status of SPS in China

Xinbin Hou 2022.5





Contents


1. Background

- 2. Development of SPS in China
- 3. Proposed roadmap on SPS
- 4. Possible Demonstration Projects



Net Zero CO₂ emission – for the future of our planet

- In 2020, President Xi Jinping announced that China would strive to peak CO₂ emissions before 2030, and achieve carbon neutrality before 2060.
- Climate change is a challenge for all of humanity. Net Zero is an urgent goal and a big challenge for all countries.
- The intermittency of the current renewable technologies makes them are not able to meet the challenges.
- There is an urgent need to develop new sources of clean energy that are sustainable, affordable, secure and scalable.




1. Background

CAST

Great news of SPS

- Positive support from government and private business
- Innovative SPS concepts

Rapid technology progress





Speedy progress of space industry

High capability and low cost of launcher

Large scale and low cost production of spacecraft



Falcon9

- Payload: 22t
- Quoted Price: \$62M
- Cost: \$20M



Falcon Heavy

- Payload : 60t
- Quoted Price : \$90M
- Cost: \$30M



Starship

- Payload : 150t
- Quoted Price : ?
- Cost Goal: \$3M



Starlink

- Mass: 250kg
- Cost : \$0.5M



Contents

- 1. Background
- 2. Development of SPS in China
- 3. Proposed roadmap on SPS
- 4. Possible Demonstration Projects


2.1 Research Activities


- China National Space Administration(CNSA) has supported the research of SPS system and key technology since 2008 and will support continuously in the next several years.
- National Natural Science Foundation of China(NSFC) has supported the fundamental research since 2015.






New Concepts





MMR-SPS, CAST, 2021




SSPS-OMEGA, Xidian University, 2014

Development Status of SPS in China – Xinbin Hou

Technologies research

- MPT is being studied and demonstrated as the most important technologies by CAST, Xidian University, Sichuan University, Chongqing University and others.
- LPT is being studied as the flexible long distant power transmission application by CAST, Beijing Institute of Technology and others.
- Advanced solar cells, high power electric equipment and large scale structure are being studied by SAST, CAST and others.



- 2. 2 Committee of Space Solar Power, Chinese Society of Astronautics
- On March 26, 2021, CSSP-CSA was established in Beijing.
- The committee invites 7 academicians as consultants, 68 committee members from 37 research institutions.
- **Prof. Ming Li was elected as the chairman of the committee.**
- The first academic conference is delayed and will be held in Chongqing. Over 200 persons and 100 papers are expected.







10 '

Development Status of SPS in China – Xinbin Hou

2.3 Experiment Bases

- A Space Solar Power Experiment Base has being set up in ChongQing since December 6, 2018. The investment will be over \$15 millions. Research fields will include Microwave Power Transmission, Laser Power Transmission, High Voltage Electric Technology, Environment Effect of High power WPT, etc.
- The infrastructure of the Space Solar Power Experiment Base will be completed soon. The basic experimental facilities will be established this year.
 Image: A Power Experiment Base will be completed soon. The basic experimental facilities will be established this year.

Development Status of SPS in China – Xinbin Hou

2.3 Experiment Bases

- The ZhuRi (Chase the Sun) Project was started in Dec. 2018. A full system, ground experimental demonstration system based on SSPS-OMEGA concept has been built.
- whole energy chain demonstration:
 - Sunlight(concentrated) DC MW Transmission DC
 - Transmission distance: 100m
 - Output DC power: 1kW
 - Transmission efficiency: 20%(DC-DC, goal).








Contents

- 1. Background
- 2. Development of SPS in China
- 3. Proposed roadmap on SPS
- 4. Possible Demonstration Projects


3. Proposed roadmap on SPS in China



Proposed Roadmap on SPS(2015)

3. Proposed roadmap on SPS in China

Revised Roadmap on SPS(draft)



Development Status of SPS in China – Xinbin Hou



Contents

- 1. Background
- 2. Development of SPS in China
- 3. Proposed roadmap on SPS
- 4. Possible Demonstration Projects

- Mission 1: High Power Electric Generation and WPT Demonstration Mission Includes 2 spacecraft in LEO and receiving system on ground to Thin Film Solar Array evaluate the validity of some key technologies of SPS in space.
 - Design principle:
 - The emphasize of the mission is to validate the theoretical energy chain and long distance beam control precision;
 - The scheme and main specifications of the solar array are based on the solar array module design of MW SPS;
 - The structure, circuit, thermal control and main electric specifications are based on the design of antenna module of MW SPS;
 - The size of microwave antenna is the tradeoff of considering the power, density and beam control.
 - The LPT is a scale full system to transmit power to the receiver on spacecraft and on ground .

MW antenna

Laser transmitter

Primary spacecraft

Receiving spacecraft

Mission specifications(draft)

- (1) Primary spacecraft
- MPT system
 - Frequency: 5.8GHz
 - RF Power: 4kW
 - Efficiency: 50%
 - Beam precision: 0.2°
- LPT system
 - Wavelength: 1064nm
 - Laser Power: 1kW
 - Efficiency : 35%
 - Beam precision : 5urad
- **D** Thin film solar array
 - Output DC power: 10kW
 - Voltage: 500V
- Concentrator solar array
 - Output DC power: 10kW
 - Concentration ratio: 4

2) Receiving spacecraft


- **Laser receiving**
 - Distance: 10km-50km
 - Laser density: 1-3 sunlight
 - Laser cell efficiency (high) : 35%
- 3) Receiver on ground
- MPT receiving
 - Distance : 400km
 - Microwave density : 30µW/m²
 - Rectenna efficiency : 6%
- **LPT receiving**
 - Distance : 400km
 - Laser cell efficiency (low) : 20%

Mission 2: GEO High Power WPT Demonstration Mission

Include 1 spacecraft in GEO and receiving system on ground to evaluate high power electric system, very long distant WPT and assembly technologies in space.

The modules are launched to LEO and assembled. The WPT experiment will be conducted in LEO firstly. Then the spacecraft will transfer to GEO and demonstrate WPT in GEO.

- Design principle :
 - The solar sub-array, the antenna module and the truss module are based on the design of MW SPS;
 - The conductive rotary joint is similar to the MW SPS ;
 - The assembly interface is similar to the MW SPS ;
 - The basic assembly technologies needs to be demonstrated ;
 - For the MPT in LEO, the power density on ground is similar to the MW SPS;
 - For the MPT in GEO, the power density on ground is similar to Mission 1.



- Mission specifications(draft)
 - (1) Spacecraft
 - MPT system
 - Frequency : 5.8GHz
 - RF Power : 100kW
 - Efficiency : 60%
 - Beam precision : 0.01°
 - **D** LPT system
 - Wavelength : 1064nm
 - Laser Power : TBD
 - Efficiency : 37%
 - Beam precision : 1urad
 - **D** Thin film solar array
 - Output power(solar array module) : 50kW
 - Voltage : 500V
 - Total DC power: 400kW
 - **High power PMAD**
 - Power of the rotary joint : 400kW
 - Voltage conversion : 500V/2kV
 - Efficiency: 97%

- 2) Receiving system
- D MPT
 - Distance (GEO) : 36000km
 - Microwave density (GEO) : $30 \mu W/m^2$
 - Rectenna efficiency (GEO) : 8%
 - Distance (LEO) : 400km
 - Microwave density (LEO) : 80mW/m²
 - Rectenna efficiency (LEO) : 60%
- LPT
 - Distance : 36000km



Thank you very much!

Please Contact: <u>houxinbin525@163.com</u>